青岛儒海船舶股份有限公司
WinKong Marine Engineering Co.，Ltd.
贻贝MarinSmart船海服务互联网平台
MARINSMART PLATFORM

Quotation

币种 Currency：

船名 **Vessel Name**	M/V DIMITRA M	**日期** **Date**	2025-12 / 2026-01
IMO No.		**船型** **Vessel Type**	82,000 mt Kamsarmax Bulk Carrier
客户名称 **Customer Name**		**港口** **Service Port**	中国区域（中/南部）港口
联系人 **Attention**		**我方报价号** **WK Offer No.**	WK-dimitra-m-2026-04-01-prod
询价号 **Your Ref No.**		**报价有效期** **Quotation Validity**	30 days
确认号 **PO No.**		**询价发起人** **PIC of WinKong**	Winkong

序号 Item	项目内容 Description	单价 Unit Price	单位 Unit	数量 Q'ty	折扣 Discount	合计 Amount
1	HCU system overhaul and calibration					
1.1	64k running hours overhaul scope for HCU system on MAN B&W 6S60ME-C8.2.	3,500.00	set	1		3,500.00
	Overhaul ELFI valve and multiway valve units					
	Overhaul exhaust valve actuator and fuel oil pressure booster					
	Overhaul cylinder lubricator system					
	Overhaul accumulator and refill with nitrogen					
	Maintenance and overhaul of HPS					
2	MPC system inspection and health check					
2.1	64k running hours inspection scope for MPC system on MAN B&W 6S60ME-C8.2.	3,500.00	set	1		3,500.00
	MPC health check					
	Inspection of MPC status and replacement readiness					
	Check UPS battery related condition					
	Dockyard management fee					
	Accommodation					
	Transportation					
	HPS accumulators repair kit (Pending confirmation)					Pending
	HCU accumulators repair kit (Pending confirmation)					Pending
	Nitrogen for refilling (Pending confirmation)					Pending
	FIVA valves pilot valves (Pending confirmation)					Pending
	Fuel booster units top covers and suction valves (Pending confirmation)					Pending
	Exhaust valve actuators safety valves (Pending confirmation)					Pending
	MPC & UPS batteries (Pending confirmation)					Pending
	Option Summary - Option 1	USD 7,000.00				Pending

总结 Summary			
服务费 Service Charge	**备件费 Spare Parts Fee**	**其它 Other**	**总计 Total**
USD 7,000.00	Pending	Pending	Pending

备注Remark

[Option 1] If the FIVA valve need to overhaul at workshop, the cost will charged extra
[Option 1] repair kits for FIVA valve
[Option 1] Warranty Compensate Amount: 5times of the service cost at max.
Spare parts warranty period shall follow supplier confirmation.
Inspection and troubleshooting items carry no service warranty.
Warranty Compensate Amount: 5 times of the service cost at max.

服务支付条款 Service Payment Terms

Payment within 30 days upon invoice date.

Cooperative Makers